

Pope Army Airfield (Pope AAF)

150-pound Halon Extinguisher Inspection, Maintenance and Testing 02 March 2023

Statement of Work (SOW)

1. SCOPE OF WORK: The contractor shall provide the 43d Aircraft Maintenance Squadron (43 AMS) all labor, tools, equipment, materials, transportation of all fire bottles, and personnel to perform off-site inspection, maintenance and testing of Wheeled 150-pound Halon Extinguishers located at Pope AAF, NC. The contractor shall perform this service in accordance with the procedures and instructions in the following publications:

1.1 Technical Order (TO) 13F4-4-121

2. SPECIFIC REQUIREMENTS:

2.1. The contractor shall provide scheduled (annual, 6 year, and 12 year) inspections, maintenance, and testing of 51 each, 150lb Halon Extinguishers IAW **TO 13F4-4-121**.

2.2. The contractor shall be aware of due and upcoming inspection, maintenance, and testing requirements, to take appropriate actions to comply with the referenced TO.

2.3. The contractor shall also provide proof of inspection, testing and maintenance as outlined in the referenced TO.

2.4. The contractor shall comply with all Federal and State regulations and/or publications related to providing maintenance on Halon Extinguishers, which include directions from the National Fire Protection Association (NFPA) and the Occupational Safety and Health Administration (OSHA).

2.5. The contractor is required to ensure that no more than 20 fire extinguishers are at the contractor's location at any given time, due to fluid mission demands of Pope AAF.

3. INSTALLATION ENTRY: Access Control procedures for entering Fort Bragg are provided at the website below. If additional assistance is required, the contractor needs to contact the 43 AMS POC, whose name and contact information will be provided in the contract award.

<https://home.army.mil/bragg/index.php/about/garrison/directorate-emergency-services/physical-security/physical-security-department-army-security-guards/access-control>

4. GENERAL REQUIREMENTS:

4.1 The contractor shall coordinate all work with the 43 AMS POC. The contractor shall provide 5-days' notice prior to work starting to allow the preparation of the equipment being tested.

4.2 Safety. The contractor shall maintain a safe and healthful working condition for all contractor personnel and must ensure conformance with standards developed under United States Public Law 91-596, OSHA standards, American National Standards Institute and NFPA.

4.3 Mishap Reporting. Report all mishaps involving any person sustaining injury or illness from contractor operations and all mishaps involving Government property or equipment damaged by the contractor to the 43 AMS POC.

(End of SOW)