

Attachment 5: Government Supplied Equipment.

1. The following work will be completed by owner.

- a. Mechanical demolition shown on MD-101
- b. Electrical demolition shown on ED-101
- c. Furnish and Install air rotation units (ARU-1, ARU-2 and ARU-3).
- d. Air rotation units control system per drawing CT-118.
- e. Chilled water piping and insulation shown on sheet M-101 and M-103
- f. Outside air ducting, fan and dampers shown on sheets M-101, M-102 and M-103.
- g. Hot water piping and insulation as shown on sheet M-101, M-102 and M-103 up to shaft . Contractor is to extend piping from shaft to third floor.

2. The following equipment will be furnished by owner and installed by contractor.

- a. AHU 1, AHU-2 AHU-3 ,AHU-4, AHU-5, AHU-6, AND AHU-7 VFD control panel will be furnished by government. Contractor to provide incoming power, network connections, and terminate all control and motor connections.
- b. Industrial Network Zone enclosures for Air Handlers AHU 1, AHU-2 AHU-3 ,AHU-4, AHU-5, AHU-6, AND AHU-7. Power and copper network connections by contractor. Fiber cabling and terminations by government.
- c. RO and Soft water skid. Control system per drawing CT-122.