

# **Questions and Vendor Clarification F3G0CA3023AW01 – 31**

## **CTS Furniture**

### **Room 171:**

#### **Questions**

- Is the Glass Clearstory to be frosted glass and not clear glass to match the glass stacks in the main area?

Yes, this glass should be frosted to match the stacks in main cubical area.

#### **Clarification**

- N/A

### **Room 147:**

#### **Questions**

- N/A

#### **Clarifications**

- 2 of the 6 areas have poles which will require special custom cuts of the short work surfaces and moving over of the overhead storage unit on 1 side to the back wall and reducing the size of the shelf.

Yes, custom cuts will be required and shorter shelves.

- From the bottom of the page, 2nd grouping of back to back stations. The station to the left of the one circled is also adding the work surfaces/shelves/overheads/pedestals. This is one of the stations with the column on the left back edge of the 24" work surface in need of a special work surface cut. The station circled on the 2nd grouping bottom is the other station with a custom cut due to a column on the far right 24" works surface. The One directly behind it on the 4th row which is circled (second aisle on top) is not included in the project as the furniture is already installed in that area. If furniture is in the area.

Worked is only required on the empty cubical areas discussed during walkthrough.

- Tack board fabric is Kio Regatta

Yes. The tack board must match the existing tack board.

- Furniture colors must match what is there now. Grey Elm laminate. Grey Elm faced Cabinets/Pedestals with Cement Trim colors.

Yes

## **Room 127:**

### **Questions**

- N/A

### **Clarifications**

- Dividing Panels will be Fabric in 64" height and will be in Fabric Kio Regatta

Yes

- Wall mounts to drywall will require extra-long mounting screws. Approx. 8" long

As long they don't penetrate through exterior walls they can be used.

- Two panels on the Main wall will be 78" tall and be in matching laminate Grey Elm

Yes

## **General:**

### **Questions**

- Will the project be done 1 room at a time and must be scheduled and coordinated for access with each area?

Grouping should be by rooms. Our mission schedule will dictate what rooms are available. Contractor needs to provide schedule in how long they think each area will take so we can block out adequate amounts of time. If the contractor can provide multiple teams for work in different areas at the same time, we can address at later time.

- What is the timeline of completion for each room in bid?

The Contractor provides the schedule and amount of time each room will take. The time each room take will be dictated by contractor workload and experience. Once government receives EDD on materials and work schedule we will schedule rooms.

## Clarifications

- Building is a secure SCIF. Installers must be US citizens and be able to pass a security clearance.

Installers must be U.S. citizens only...no dual citizenship. The security checks required to enter the installation require that installers do not have warrants out for their arrest.

- No smart electronics are allowed in the SCIF. NO cell phones, Bluetooth, certain key fobs, certain medical devices are not allowed (ie electronic insulin pumps) or anything wifi capable

Not allowed. Any item that transmits a signal is not allowed.