MATCHLINE AREA A

MATCHLINE AREA B

ELEC
03-SV-F6-E3

75.0' (5363.0' USGS) CENTERLINE OF PENETRATION.

1 1/2"IRW TO IRRIGATION SYSTEM MINIMUM 5 FT BELOW FINISHED GRADE. COORDINATE EXACT LOCATION & REQUIREMENTS W/ IRRIGATION. RE: IRRIGATION DWGS.

PROVIDE (N) FREEZELESS YARD HYDRANT

P-806

1 1/2"IRW

P-420

P-608

1 1/2"IRW DN FROM LEVEL ABOVE TO DN BELOW FLOOR.

(N) 3/4"DCW DN IN WALL TO UNDER SERVICE LEVEL AND OUT TO (N) YARD HYDRANT.

ELEC
03-SV-B7-E4

DATA / TELECOMM
03-SV-B7-T3

ELEV
03-SV-SE6

ELEV
03-SV-SE7

P-422

P-807
P-408

1"DCW, 3/4"DWH, AND (2) 1 1/4" DI UNDER SLAB TO ISLAND.

1 1/4"DI WATER

INSTALL 12" METAL LADDER RUNGS AT 12" OC INTO VAULT BELOW

P-701

P-101

P-408

P-103

P-701

P-528

P-408

P-101

P408

BOILER CONTROL ROOM.) PROVIDE CONNECTION TO BUILDING AUTOMATION SYSTEM.

03-MAP-2

TP-1 TRAP PRIMER. EXTEND 1/2" TO EACH FD. 1 1/2"IRW UP TO LEVEL ABOVE.

P-804

MECH
03-MT1

1 1/2" IRRIGATION REDUCED PRESSURE BACKFLOW PREVENTER

IRRIGATION METER

1 1/2"DCW DN FROM LEVEL ABOVE.

STAIR
03-SV-ST3

DENTAL HIGH VOLUME ORAL EVACUATION SYSTEM

03-DVP-1

STAIR
03-SV-ST5

one eighth inch = one foot

0 4 8 16

## 1 SERVICE LEVEL PLUMBING PIPING PLAN - AREA B

1/8" = 1'-0"

NORTH

| Revisions | Date |
|---|---|
| | |

CONSULTANTS:

Professional Seal

ARCHITECT/ENGINEERS:

Key Plan

Drawing Title: DIAGNOSTIC AND TREATMENT SERVICE LEVEL PLUMBING PIPING PLAN - AREA B

Approved: Project Director

Project Title: REPLACEMENT MEDICAL CENTER FACILITY, EASTERN COLORADO HEALTH CARE SYSTEM

Location: AURORA, COLORADO

Date: 08/26/2021

Checked

Drawn

Project Number: 554-501

Building Number: 03

Drawing Number: 03.PP.100-B

OFFICE OF CONSTRUCTION AND FACILITIES MANAGEMENT

Department of Veterans Affairs

01 - CON | 02 - RES | 04 - IBS | 05 - IBN | 06 - ENC | 07 - CLC | 08 - CBN | 09 - CBC | 10 - CBS | 11 - PSN | 12 - PVN | 13 - PVS