

Amendment to a Previous Combined Solicitation A00001

PLEASE NOTE: 36C25623Q1526 IS CANCELLED

SUBJECT Climate Control Portable Office Building -Pre-fabricated Warehouse Office Cubicle
T*

GENERAL INFORMATION

CONTRACTING OFFICE'S ZIP CODE*	70112
SOLICITATION NUMBER*	36C25623Q1676
RESPONSE DATE/TIME/ZONE	08-24-2023 5:00 EASTERN TIME, NEW YORK, USA
ARCHIVE	90 DAYS AFTER THE RESPONSE DATE
RECOVERY ACT FUNDS	N
SET-ASIDE	SDVOSB
PRODUCT SERVICE CODE*	5410
NAICS CODE*	332311
CONTRACTING OFFICE ADDRESS	Department of Veterans Affairs Southeast Louisiana Veterans HCS 1515 Poydras Street New Orleans LA 70112
POINT OF CONTACT*	CONTRACT SPECIALIST DEBRA JAMES debra.james3@va.gov 504-380-2553

PLACE OF PERFORMANCE

ADDRESS	1100 N. College Avenue Attn: Warehouse Building 8
----------------	--

*= Required Field

Amendment to a Previous Combined Solicitation

Amendment to a Previous Combined Solicitation

	Fayetteville Arkansas
POSTAL CODE	72703
COUNTRY	USA

ADDITIONAL INFORMATION

AGENCY'S URL	https://www.va.gov
URL DESCRIPTION	Department of Veterans Affairs
AGENCY CONTACT'S EMAIL ADDRESS	
EMAIL DESCRIPTION	

Amendment to a Previous Combined Solicitation

DESCRIPTION

AMENDMENT A00001 36C25623Q1676

SUBJECT* Climate Controlled Portable Office building L20' X W25' X H

SOLICITATION CLOSING DATE UPDATED TO AUGUST 24, 2023 5:00 EST

Delivery address:

Questions

The number of doors? Number of Windows? Interior finish?

Requested date for delivery?

Any specifications will be helpful.

What type of setup and utilities are required for this? Or is it simply the supply of a portable office building without the installation? Also, on SAM.GOV, there is only one document which is titled an amendment. Is there an associated Form 1449 or other RFQ-type documents to provide the pricing? Page 7 of 36C25623Q1676 the Combined Synopsis/Solicitation Notice is where the pricing can be filled in. You may add an extra page if needed. Please notate your pricing.

There are two sets of double doors on the north most wall and the west most wall on the southmost corner 6068 Heavy Duty Aluminum, half glass, clear anodized finish. There will be 4 glass panes in the doors that will be clear tempered safety glass, the doors will utilize a lever lockset/ Lever passage as the opening mechanism. There are 5 horizontal sliding windows that will be clear tempered safety glass. Three windows will be placed along the west wall and two windows will be placed on the north wall of the new office space. The utilities that will be used in this project will be data and electric. All of the utilities will be ran to a subpanel located on the northmost wall on the east most corner. The power will be provided by the facility, run to the subpanel by the VA electricians and the data cable will be ran by the special systems. The utilities will include 6EA 2 X 4 flat panel LED lights

2EA 3-way light switches located next to the doors on the inside

10EA 115v Duplex Outlet (3 west, 2 north, 4 east, 1 south)

1EA 230v Single Outlet (1 south)

8EA Phone/Data Jack (4 East, 2 South, 2 North)

1EA 125-amp single phase 12 circuit load center (Subpanel). The Utilities will include climate control utilizing the specifications below:

1EA B71-913 AOU24RLXFZ MINI-SPLIT HEAT PUMP MULTI-ZONE OUTDOOR FUJITSU 22K BTUH 208/230V R410A

2EA B64-841 ASUH12LPAS MINI-SPLIT HEAT PUMP SINGLE OR MULTI-ZONE INDOOR WALL MOUNTED FUJITSU 12K BTUH 20SEER 208/230V R410A

2EA B72-489 40620500B3B6 LINE SET MINI-SPLIT 1/4IN 3/8IN 1/2IN SOFT STRAIGHT END WITH FLARE NUTS

2EA G35-702 UTY-RNNUM WIRED REMOTE CONTROL