

Amendment to a Previous Combined Solicitation A00002

PLEASE NOTE: 36C25623Q1526 IS CANCELLED

SUBJECT Climate Control Portable Office Building -Pre-fabricated Warehouse Office Cubicle
T*

GENERAL INFORMATION

CONTRACTING OFFICE'S ZIP CODE*	70112
SOLICITATION NUMBER*	36C25623Q1676
RESPONSE DATE/TIME/ZONE	08-24-2023 5:00 EASTERN TIME, NEW YORK, USA
ARCHIVE	90 DAYS AFTER THE RESPONSE DATE
RECOVERY ACT FUNDS	N
SET-ASIDE	SDVOSB
PRODUCT SERVICE CODE*	5410
NAICS CODE*	332311
CONTRACTING OFFICE ADDRESS	Department of Veterans Affairs Southeast Louisiana Veterans HCS 1515 Poydras Street New Orleans LA 70112
POINT OF CONTACT*	CONTRACT SPECIALIST DEBRA JAMES debra.james3@va.gov 504-380-2553

PLACE OF PERFORMANCE

ADDRESS	1100 N. College Avenue Attn: Warehouse Building 8
----------------	--

*= Required Field

Amendment to a Previous Combined Solicitation

Amendment to a Previous Combined Solicitation

	Fayetteville Arkansas
POSTAL CODE	72703
COUNTRY	USA

ADDITIONAL INFORMATION

AGENCY'S URL	https://www.va.gov
URL DESCRIPTION	Department of Veterans Affairs
AGENCY CONTACT'S EMAIL ADDRESS	
EMAIL DESCRIPTION	

Amendment to a Previous Combined Solicitation

DESCRIPTION

AMENDMENT A00002 36C25623Q1676

SUBJECT*

Climate Controlled Portable Office building L20' X W25' X H

**SOLICITATION CLOSING DATE UPDATED TO AUGUST 24,
2023 5:00 EST**

Delivery address:

1. Is there a rollup door at least 20' wide to get the unit inside the warehouse?
No, there is a rollup door that is 12' tall and 7'10" wide
2. Can you please provide the manufacturer which the specifications are written around.
The manufacturer that we wrote the specifications around was PortaKing.
1. Do you have further specifications as to the build out of the office space, such as number of offices needed, power and data requirements, or is this simply for storage of lab and pharmacy materials?
This office space will be essentially an open room for the warehouse to operate inside and receive materials. It will require no inside partitions or separation through the space. The idea is for it to be a bullpen the materials handlers to bring carts of supplies to receive through the double doors where they can open the packages to verify the correct items were shipped. The power is to use modular wiring run to a subpanel and the data will have ports made and the VA will run the data cabling.
2. Can you provide the location on the campus the temporary facility will be located and where the power can be tied in?
The location on campus is building 8 on the top side this is not a temporary facility however this plan is designed to be a permanent solution to provide the employees with a suitable climate controlled area to accomplish their work. The power will be tied in to the existing building power panel however the VA electricians will be the ones connecting the power from the main panel to the sub panel. All of the power requirements for this project should be modularly wired to a subpanel the VA electricians will then "plug into" after the office space is constructed.

TO OFFERORS: PLEASE FILL IN YOUR PRICING IN THE 36C25623Q1676. PLEASE SEE PAGE 7 FROM THE COMBINED SYNOPSIS/SOLICITATION NOTICE.