

SPECIFICATION SHEET
Mountain Home AFB, ID
Crash Trailer
16 November 2022

1. GENERAL: The 366th Fighter Wing Crash Recovery Section located on Mountain Home AFB, ID requires a Goose-neck trailer for transporting Crash Recovery Tools to and from crash site/emergency site.

2. TRAILER MINIMUM SPECIFICATIONS: The 48' Goose-neck Trailer must (at a minimum) comply with the following salient characteristics:

2.1. Physical Characteristics

- 2.1.1. 8'6" x 48' Gooseneck Auto Hauler, 40' Box, 8' Gooseneck
GVWR 21000#, 3-7000# 8-Lug Axels, ST235/80-16" Radial Tires, 6-Wheel Brakes
- 2.1.2. Triple 7K Axles
- 2.1.3. 7' Inside Height
- 2.1.4. 4' Beavertail
- 2.1.5. Rear Ramp Door (84" Clearance Height)
- 2.1.6. 36" Aluminum Side Door w/Dead Bolt
- 2.1.7. 2 5/16" adjustable coupler
- 2.1.8. Dual 10000# Dropleg Jacks - Set of 2
- 2.1.9. Polybead Floor I.L.O. 3/4" Plywood
- 2.1.10. 1/4" plywood walls
- 2.1.11. White Vinyl Ceiling Liner
- 2.1.12. R-6 Insulated Walls and Ceiling
- 2.1.13. Upper and Lower Nose Cabinets with Countertop
- 2.1.14. Integrated Toolbox in Lower Cabinet
- 2.1.15. 24" x 72" 3 Tier Shelving unit
- 2.1.16. E-Track Recessed on Wall P/S and D/S wall
- 2.1.17. D-Rings 6K# Rated Recessed Swivel
- 2.1.18. 110 Pkg with 30 Amp Service
Includes: 30 Amp Breaker Panel, 30 Amp Service Cord, 4 - Interior Duplex Receptacles, 1 - Exterior Gfi Duplex Receptacles, 4 -48" LED Light Fixtures, Single Light Switch

2.1.19. TRANSFER SWITCH

2.1.20. 3600 Watt Generator - Requires Propane Pkg

2.1.21. 15K BTU Air Conditioner with Thermostat (Requires 110 Pkg)

2.1.22. 42,000 BTU Ducted Air Furnace - Includes: Dual 7.5 Gallon Propane Tanks

2.1.23. 40 Gallon Fuel Station

Includes: Fuel Pump, Fuel Gauge, Gas Hose, Nozzle, Ground, Lockable Storage

2.1.24. DUAL 12V DEEP CYCLE BATTERIES W/BOX, BATTERY DISCONNECT

2.2. Warranty

2.2.1. Structural: 5 years

2.2.2. Additional Components: Separate manufacture warranties per item

3. INSTALLATION: The Contractor shall provide all personnel, equipment, tools, materials, supervision, transportation, and other items needed to build the trailer

3.1. The Contractor shall install all requested equipment in accordance with (IAW) manufacturer's specifications.

3.2. The Contractor shall ensure proper operation of the installed components.

3.3. Any equipment not functioning properly IAW manufacture's specifications shall be diagnosed and repaired by the Contractor.