

G644 Lighting Inverter Replacement**General Intent:**

The intent of this project is to remove the existing lighting inverter and replace with the same model inverter listed below in the contractor responsibility requirements.

Project Area Descriptions

Bldg. G644 is an Academic facility located at G644 "D" Street. The building will be occupied while project is completed. The point of contact for access to the building and scheduling is Marco Flores at (910) 449-0263 or marco.flores@usmc.mil

Contractor Responsibility and Requirements**Electrical**

The Contractor Shall-

1. Remove and dispose of the existing Model ELE-JYX-18KW-1S10 Controlled Power Company lighting inverter. This includes the inverter and battery cabinet complete. Properly dispose of all hazardous materials.
2. Install new lighting inverter and battery cabinet per manufacturer's instruction. Perform factory authorized start-up of the new unit.