

October 27, 2022

Addendum to Bid Specifications:

XTLF21-1045PA Repair Pavements – Brown Parkway Westbound, B07161, Ph 1
XTLF21-1045PB Repair Pavements – Brown Parkway Eastbound, B07161, Ph 2
XTLF23-1016 Construct Sidewalks, B07191
XTLF24-1020 Construct Club Access Road, B07161

Delete the Schedule C sheets in the specifications, pdf page 34 thru page 37.

Replace with the following sheets. (total of 7 sheets)

A separate file, in Microsoft excel, is also also part of this addendum)

SCHEDULE C
SUMMARY SHEET

Insert values from the individual project schedule C's into the table below.

Project Number	Base Bid	Alternate Bid
XTLF 21-1045PA		
XTLF 21-1045PB		
XTLF 23-1016		-
XTLF 24-1020		
TOTAL		

Notes :

- 1- Base bid with AC concrete.
- 2- Alternate bid with PCC concrete.

XTLF 21-1045PA REPAIR PAVEMENTS - BROWN PARKWAY WESTBOUD, B07161, PHASE 1
SCHEDULE C

PAY ITEMS-REPAIR PAVEMENTS BROWN PARKWAY , WESTBOUND, B07161, PH1									
BASE BID - ASPHALT PAVEMENT ALTERNATE BID - CONCRETE PAVEMENT									
PAY ITEM NO.	ODOT ITEM NO.	ITEM DESCRIPTION	NOTES	UNIT	QUANTITY		TOTAL		
					BASE	ALT.	BASE BID		ALT.
1	210(A)	CLEARING AND GRUBBING	(6)	LSUM	1.00	1.00			
2	202(A)	UNCLASSIFIED EXCAVATION	(R-2)(1)	CY	95.00	95.00			
3	202(D)	UNCLASSIFIED BORROW	(R-2)(R-3)(1)	CY	706.00	706.00			
4	205(A)	TYPE A-SALVAGED TOPSOIL	(R-4)	LSUM	1.00	1.00			
5	221(F)	TEMPORARY ROCK FILTER DAM TYPE 4		CY	368.00	368.00			
6	221(H)	(SP) TEMPORARY INLET SEDIMENT FILTER	(R-8)(2)	EA	14.00	14.00			
7	240(A)	REMOVING TREES 19" TO 24" IN DIAMETER		EA	4.00	4.00			
8	242	(PL) STABILIZED CONSTRUCTION EXIT		EA	1.00	1.00			
9	303(A)	AGGREGATE BASE TYPE A		CY	701.00	462.66			
10	307(H)	LIME STABILIZED SUBGRADE		SY	3162.22	3162.22			
11	326(A)	GEOTEXTILE REINFORCEMENT		SY	3162.22	3162.22			
12	407(B)	TACK COAT	(R-24)	GAL	474.33	0.00			
13	408	PRIME COAT	(R-21)	GAL	316.22	0.00			
14	411(B)	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-25)	TON	531.25	0.00			
15	411(C)	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-25)	TON	531.25	0.00			
16	414(B)	DOWEL JOINTED P.C.C. PAVT. (PLACEMENT)	(R-25)	SY	0.00	3162.22			
17	509(B)	CLASS A CONCRETE		CY	0.00	527.04			
18	609(B)	1'-8" COMB. CURB & GUTTER (6" BARRIER)		LF	2273.00	2273.00			
19	610(A)	4' CONCRETE SIDEWALK		SY	26.00	26.00			
20	611(A)	MANHOLE (4' DIAMETER)	(R-33)	EA	9.00	9.00			
21	611(G)	INLET CI DES.2 (STD)	(R-32)(R-33)	EA	15.00	15.00			
22	611(G)	INLET CDI RCB DES. 5		EA	1.00	2.00			
23	611(G)	INLET CDI RCB DES. 6 (TEMPORARY STRUCTURE)		EA	1.00	2.00			
23	613(E)	12" CORRUGATED METAL PIPE		LF	30.00	30.00			

Schedule C continued on next page

XTLF 21-1045PA REPAIR PAVEMENTS - BROWN PARKWAY WESTBOUD, B07161, PHASE 1
SCHEDULE C

24	613(E)	18" CORRUGATED METAL PIPE		LF	66.00	66.00	
25	613(A)	18" R.C.PIPES CLASS IV		LF	709.00	709.00	
26	613(A)	24" R.C.PIPES CLASS IV		LF	390.00	390.00	
27	619(B)	REMOVAL OF CURB AND GUTTER	(R-38)(R-39)	LF	2330.00	2330.00	
28	619(B)	REMOVAL OF ASPHALT PAVEMENT	(R-38)(R-39)	SY	3378.22	3378.22	
29	619(B)	REMOVAL OF DRAINAGE INLETS	(R-38)(R-39)	EA	6.00	6.00	
30	619(B)	REMOVAL OF MANHOLES	(R-38)(R-39)	EA	2.00	2.00	
31	619(B)	REMOVAL OF SIDEWALK	(R-38)(R-39)	SY	23.33	23.33	
32	619(B)	REMOVAL OF EXISTING PIPE	(R-38)(R-39)	LF	777.00	777.00	
33	619(C)	SAWING PAVEMENT		LF	336.00	336.00	
34	641	MOBILIZATION		LSUM	1.00	1.00	
35	642(A)	CONSTRUCTION STAKING LEVEL I		LSUM	1.00	1.00	
36	805(A)	REMOVAL OF EXISTING SIGNS		LSUM	1.00	1.00	
37	805(D)	REMOVE AND STORE GROUND MOUNTED FLAG POLES		EA	41.00	6.00	
38	805(D)	REMOVE AND RESET GROUND MOUNTED SIGN		EA	1.00	1.00	
39	850(A)	SHEET ALUMINUM SIGNS	(TS-34)	SF	47.29	47.29	
40	851(C)	2 1/4" SQUARE TUBE POST	(TS-33)	LF	34.00	34.00	
41	851(C)	2 1/2" SQUARE TUBE POST	(TS-33)	LF	46.50	46.50	
42	854(A)	TRAFFIC STRIPE (MULTI-POLY) (6" WIDE)	(TS-24)	LF	505.00	505.00	
43	854(A)	TRAFFIC STRIPE (MULTI-POLY) (24" WIDE)	(TS-24)	LF	88.00	88.00	
43	854(B)	TRAFFIC STRIPE (MULTI-POLY) (ARROW)		EA	28.00	28.00	
44	854(B)	TRAFFIC STRIPE (MULTI-POLY) (SYMBOLS)		EA	6.00	6.00	
45	854(B)	TRAFFIC STRIPE (MULTI-POLY) (WORDS)		EA	4.00	4.00	
46	880(J)	CONSTRUCTION TRAFFIC CONTROL	(TC-25)(TC-33)	LSUM	1.00	1.00	
47	SP	BONDS AND INSURANCE		LSUM	1.00	1.00	

BASE BID TOTAL =

ALTERNATE BID TOTAL =

XTLF 21-1045PB REPAIR PAVEMENTS - BROWN PARKWAY EASTBOUD, B07161, PHASE 2
SCHEDULE C

PAY ITEMS-BROWN PARKWAY EASTBOUND. B07161, PH2									
BASE BID - ASPHALT PAVEMENT ALTERNATE BID - CONCRETE PAVEMENT									
PAY ITEM NO.	ODOT ITEM NO.	ITEM DESCRIPTION	NOTES	UNIT	QUANTITY		TOTAL		
					BASE BID	ALT.	BASE BID		ALT.
1	210(A)	CLEARING AND GRUBBING	(6)	LSUM	1.00	1.00			
2	202(A)	UNCLASSIFIED EXCAVATION	(R-2)(1)	CY	514.00	95.00			
3	202(D)	UNCLASSIFIED BORROW	(R-2)(R-3)(1)	CY	609.00	706.00			
4	205(A)	TYPE A-SALVAGED TOPSOIL	(R-4)	LSUM	1.00	1.00			
	221(F)	TEMPORARY ROCK FILTER DAM TYPE 4		CY	339.00	339.00			
5	221(H)	(SP) TEMPORARY INLET SEDIMENT FILTER	(R-8)(2)	EA	12.00	12.00			
6	240(A)	REMOVING TREES 19" TO 24" IN DIAMETER		EA	4.00	4.00			
7	242	(PL) STABILIZED CONSTRUCTION EXIT		EA	1.00	1.00			
8	303(A)	AGGREGATE BASE TYPE A		CY	756.43	499.24			
9	307(H)	LIME STABILIZED SUBGRADE		SY	3593.44	3593.44			
10	326(A)	GEOTEXTILE REINFORCEMENT		SY	3593.44	3593.44			
11	407(B)	TACK COAT	(R-24)	GAL	539.02	0.00			
12	408	PRIME COAT	(R-21)	GAL	359.34	0.00			
13	411(B)	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-25)	TON	603.70	0.00			
14	411(C)	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-25)	TON	603.70	0.00			
15	414(B)	DOWEL JOINTED P.C.C. PAVT. (PLACEMENT)	(R-25)	SY	0.00	3593.44			
16	509(B)	CLASS "A" CONCRETE		CY	0.00	598.91			
17	609(B)	1'-8" COMB. CURB & GUTTER (6" BARRIER)		LF	1538.00	1538.00			
18	610(A)	4" CONCRETE SIDEWALK		SY	73.00	73.00			
19	611(A)	MANHOLE (4' DIAMETER)	(R-33)	EA	2.00	2.00			
20	611(A)	MANHOLE (6' DIAMETER)	(R-33)	EA	2.00	2.00			
21	611(G)	INLET CI DES.2 (STD)	(R-32)(R-33)	EA	7.00	7.00			
22	611(G)	INLET CDI RCB DES.5		EA	1.00	1.00			
23	613(A)	18" R.C.PIPE CLASS IV		LF	483.00	483.00			
24	613(A)	24" R.C.PIPE CLASS IV		LF	55.00	55.00			

Schedule C continued on next page

XTLF 21-1045PB REPAIR PAVEMENTS - BROWN PARKWAY EASTBOUD, B07161, PHASE 2
SCHEDULE C

25	613(A)	48" R.C. PIPE CLASS IV		LF	30.00	30.00	
26	619(B)	REMOVAL OF CURB AND GUTTER	(R-38)(R-39)	LF	1430.00	1430.00	
27	619(B)	REMOVAL OF CONCRETE PAVEMENT	(R-38)(R-39)	SY	84.04	84.04	
28	619(B)	REMOVAL OF ASPHALT PAVEMENT	(R-38)(R-39)	SY	4243.33	4243.33	
29	619(B)	REMOVAL OF DRAINAGE INLETS	(R-38)(R-39)	EA	7.00	7.00	
30	619(B)	REMOVAL OF MANHOLES	(R-38)(R-39)	EA	2.00	2.00	
31	619(B)	REMOVAL OF SIDEWALK	(R-38)(R-39)	SY	290.00	23.33	
32	619(B)	REMOVAL OF EXISTING PIPE	(R-38)(R-39)	LF	467.00	467.00	
33	619(C)	SAWING PAVEMENT		LF	141.00	141.00	
34	641	MOBILIZATION		LSUM	1.00	1.00	
35	642(A)	CONSTRUCTION STAKING LEVEL I		LSUM	1.00	1.00	
36	804(A)	STRUCTURAL CONCRETE CLASS A		CY	1.04	1.04	
37	804(B)	REINFORCING STEEL		LB	152.00	152.00	
38	805(A)	REMOVAL OF EXISTING SIGNS		LSUM	1.00	1.00	
39	805(D)	REMOVE AND RESET GROUND MOUNTED SIGN		EA	1.00	1.00	
40	850(A)	SHEET ALUMINUM SIGNS	(TS-34)	SF	150.89	150.89	
41	851(B)	3-1/2" @9.11 GALV. STEEL PIPE POST	(TS-33)	LF	71.00	71.00	
42	851(C)	2 1/4" SQUARE TUBE POST	(TS-33)	LF	22.00	22.00	
43	851(C)	2 1/2" SQUARE TUBE POST	(TS-33)	LF	31.00	31.00	
44	856(A)	TRAFFIC STRIPE (MULTI-POLY) (6" WIDE)	(TS-24)	LF	795.00	795.00	
45	856(A)	TRAFFIC STRIPE (MULTI-POLY) (24" WIDE)	(TS-28)	LF	203.00	203.00	
46	856(B)	TRAFFIC STRIPE (MULTI-POLY) (ARROW)		EA	8.00	8.00	
47	857(B)	TRAFFIC STRIPE (MULTI-POLY) (SYMBOLS)		EA	11.00	11.00	
48	857(B)	TRAFFIC STRIPE (MULTI-POLY) (WORDS)		EA	11.00	11.00	
49	880(J)	CONSTRUCTION TRAFFIC CONTROL	(TC-25)(TC-33)	LSUM	1.00	1.00	
50	SP	BONDS AND INSURANCE		LSUM	1.00	1.00	

BASE BID TOTAL =

ALTERNATE BID TOTAL =

XTLF 23-1016 CONSTRUC SIDEWALKS, B07191
SCHEDULE C

PAY ITEMS - CONSTRUCT SIDEWALKS, B07191							
PAY ITEM NO.	ODOT ITEM NO.	ITEM DESCRIPTION	NOTES	UNIT	QUANTITY	UNIT PRICE	COST
1	610(A)	4' CONCRETE SIDEWALK		SY	1096.00		
2	641	MOBILIZATION		LSUM	1.00		
3	642(A)	CONSTRUCTION STAKING LEVEL I		LSUM	1.00		
4	802(B)	1-1/2" PVC SCH. 40 PLASTIC CONDUIT BORED		LF	3400.00		
5	802(B)	1-1/2" PVC SCH. 40 PLASTIC CONDUIT TRENCHED		LF	550.00		
6	803(A)	PULL BOXES (SIZE I)		EA	14.00		
7	804(A)	CLASS "A" CONCRETE		CY	1.56		
8	804(B)	REINFORCING STEEL		LB	228.00		
9	806(D)	(SP)LIGHTED BOLLARD	(101)	EA	134.00		
10	811	1/C NO.8 ELECT. COND.		LF	28000.00		
11	811	1/C NO.10 ELECT. COND.		LF	13500.00		
12	850(A)	SHEET ALUMINUM SIGNS	(TS-34)	SF	96.00		
13	850(D)	SPECIAL SIGNS	(102)	SF	108.00		
14	851(B)	3-1/2"@9.11 GALV. STEEL PIPE "A"	(TS-33)	LF	99.00		
15	851(C)	2-1/2" SQUARE TUBE POSE	(TS-33)	LF	60.00		
16	880(J)	CONSTRUCTION TRAFFIC CONTROL	(TC-25)(TC-33)	LSUM	1.00		
17	SP	BONDS AND INSURANCE		LSUM	1.00		
18	SP	PROTECTION BARRIER-OPTION 1 (PLANTERS WITH LIGHTED BOLLARDS)		LSUM	1.00		

BID TOTAL =
 =====

XTLF 24-1020 CONSTRUCT CLUB ACCESS ROAD, B07161
SCHEDULE C

PAY ITEMS - CONSTRUCT CLUB ACCESS ROAD, B07161									
BASE BID - ASPHALT PAVEMENT ALTERNATE BID - CONCRETE PAVEMENT									
PAY ITEM NO.	ODOT ITEM NO.	ITEM DESCRIPTION	NOTES	UNIT	QUANTITY		TOTAL		
					BASE BID	ALT.	BASE BID		ALTERNATE BID
1	210(A)	CLEARING AND GRUBBING	(6)	LSUM	1.00	1.00			
2	202(A)	UNCLASSIFIED EXCAVATION	(R-2)(1)	CY	25.00	25.00			
3	202(D)	UNCLASSIFIED BORROW	(R-2)(R-3)(1)	CY	25.00	25.00			
4	205(A)	TYPE A-SALVAGED TOPSOIL	(R-4)	LSUM	1.00	1.00			
5	221(H)	(SP) TEMPORARY INLET SEDIMENT FILTER	(R-8)(2)	EA	2.00	2.00			
6	240(A)	REMOVING TREES 19" TO 24" IN DIAMETER		EA	2.00	2.00			
7	242	(PL) STABILIZED CONSTRUCTION EXIT		EA	1.00	1.00			
8	303(A)	AGGREGATE BASE TYPE A		CY	129.89	85.73			
9	307(H)	LIME STABILIZED SUBGRADE		SY	779.33	779.33			
10	326(A)	GEOTEXTILE REINFORCEMENT		SY	779.33	779.33			
11	407(B)	TACK COAT	(R-24)	GAL	116.90	0.00			
12	408	PRIME COAT	(R-21)	GAL	77.93	0.00			
13	411(B)	SUPERPAVE, TYPE S3 (PG 64-22 OK)	(R-25)	TON	130.93	0.00			
14	411(C)	SUPERPAVE, TYPE S4 (PG 64-22 OK)	(R-25)	TON	130.93	0.00			
15	414(B)	DOWEL JOINTED P.C.C. PAVT. (PLACEMENT)		SY	0.00	779.33			
16	509(B)	CLASS A CONCRETE		CY	0.00	389.67			
17	609(B)	1'-8" COMB. CURB & GUTTER (6" BARRIER)		LF	676.00	676.00			
18	619(B)	REMOVAL OF CURB AND GUTTER	(R-38)(R-39)	LF	200.00	200.00			
19	619(B)	REMOVAL OF ASPHALT PAVEMENT	(R-38)(R-39)	SY	70.33	70.33			
20	619(C)	SAWING PAVEMENT		LF	141.00	141.00			
21	641	MOBILIZATION		LSUM	1.00	1.00			
22	642(A)	CONSTRUCTION STAKING LEVEL I		LSUM	1.00	1.00			
23	880(J)	CONSTRUCTION TRAFFIC CONTROL	(TC-25)(TC-33)	LSUM	1.00	1.00			
24	SP	BONDS AND INSURANCE		LSUM	1.00	1.00			

BASE BID TOTAL =

ALTERNATE BID TOTAL =