BASELINE CONTROL		
CONTROL POINT	BEARING	DISTANCE
1-2	S39°32'04"W	773.71
2-3	N77°02'39"W	106.71
3-4	N05°58'52"E	521.71
4-5	N51°12'06"E	546.61
5-6	S03°15'10"W	188.67
6-1	S51°35'00"E	142.65

ELEV. CONTROL
BM. 1, 3" ALUMINUM CAP SET IN GROUND, ELEV. 919.38
(BM. 1 IS ALSO CONTROL PT. 6)



FUTURE ROAD WIDENING BY COUNTY

N51°12'06"E 546.61'

COR. 5
S22°00'00"E 311.85'
COR. 1

K.U. ELECTRIC METER

22" x 18' CMPA

PROPOSED ADDITION 45' x 28'

TO BE RELOCATED

WOODS

UNDER GROUND TELEPHONE LINE

3" ALUMINUM CAP 919.38

BM. 1

C.O.

TO BE ABANDONED

MH

920

915

910

925

WOODS

UNDER GROUND ELECT. LINE

F.D.R. 798

CONC. PAVED

BORE UNDER ROAD

CONNECT TO EXIST. LINE

LONDON UTILITIES CO. 10" SEWER

N05°58'52"E 521.71'

PROPERTY LINE AND SITE BOUNDARY LINE

FUTURE LINE CONNECTION

MH

CONC. PAVED

GARAGE WORKSHOP 04 / 33 FL. ELEV. 922.4

C.O.

3 PHASE 208

COR. 2

COR. 3

N77°02'39"W 106.71'

S39°32'04"W 773.71'

WATER LINE TO DISPOSAL FIELD

LONDON UTILITIES CO. WATER MAIN

TELEPHONE CO.

NOTES:
1. SITE IS ENTIRELY SURROUNDED BY PRIVATE LANDS.
2. SITE BOUNDARY LINES ARE SAME AS PROPERTY LINES.
3. PROPERTY CORNERS 1-5 ARE ALSO BASELINE CONTROL.
4. POWER IS 3 PHASE 208 V KY. UTILITIES CO.
5. TELEPHONE IS KY. TELEPHONE CO.

LEGEND

WATER LINE	
FIRE HYDRANT	
SEPTIC TANK	
SEWER LINE	
TERRITORIAL LINE	
TELEPHONE LINE	
POWER LINE	
UTILITY POLE	
CONCRETE WALK	
GAS LINE	
UNDERGROUND INTERCOM	
IMPROVED ROAD	
UNDERGROUND POWER	
RADIO ANTENNA	
FLAG POLE	
GAS METER	
FIXED GUST	
DISTRICT SIGN	
RADIO ANT.-AIR NET	
GATE STOP POST	
MANHOLE (PROPOSED)	MH
PROPOSED SEWER	
PROPOSED CLEANOUT	CO

PLANT LIST

KEY/SCIENTIFIC NAME	COMMON NAME
1. TAXUS BROWNII	BROWNS YEW
2. MAHONIA AQUIFOLIUM	OREGON HOLLYGRAPE
3. EUONYMUS CARRIERI	GLOSSY WINTER CREEPERY
4. LIGUSTRUM REGELIANUM	REGEL PRIVET
5. TAXUS CUSPIDATA CAPITATA	UPRIGHT JAPANESE YEW
6. TAXUS CUSPIDATA	SPREADING JAPANESE YEW
7. ENONYMUS ALATUS COMPACTA	DWARF WINGED ENONYMUS
8. ILEX ROTUNDIFOLIA	JAPANESE HOLLY
9. BUXUS SEMPERVIRENS	COMMON BOX
10. LONICERA MORROWI	MORROW HONEYSUCKLE
11. VIBURNUM TOMENTOSUM	DOUBLE FILE VIBURNUM
12. FORSYTHIA SPECTABILIS	BORDER FORSYTHIA
13. VIBURNUM BURKWOODI	BURKWOOD VIBURNUM
14. JUNIPERUS PFITZERIANA	PFITZER JUNIPER

CORRECTIONS

FOR MONTH	1973 YEAR
July	1975

APPROVED _____ DISTRICT RANGER _____ DATE
APPROVED _____ FOREST SUPERVISOR _____ DATE
APPROVED _____ REGIONAL ENGINEER _____ DATE
APPROVED _____ ASST. REG. FOR., OPERATION _____ DATE
APPROVED _____ ASST. REG. FOR., RECREATION & WATERSHED _____ DATE

U. S. DEPARTMENT OF AGRICULTURE
FOREST SERVICE
REGION 9
JOHN A. ADAMS - REGIONAL ENGINEER

DANIEL BOONE NATIONAL FOREST
LONDON ADMINISTRATIVE SITE
SITE SURVEY PLAT

DESIGNED D.B.N.F. DRAWN R.D.H.
SCALE 1" = 30' CHECKED D.L.H.
APPROVED _____ FOREST ENGINEER DATE
SHEET 1 OF 1 DWG.

Distegon N. O. 1984 "Aquarion"

PRELIMINARY SITE DEVELOPMENT PLAN

LONDON OFFICE ADDITION

APPENDIX G

8-85