

PART I - THE SCHEDULE  
SECTION A –ITEMS

**Pre-Demolition Abatement Contract  
Group 5**

SUMMARY SCHEDULE OF ITEMS

Item No./Title	Description	Qty	Total Cost
1. Asbestos Analysis/Certification	Provide ACM inspection performed and signed by an Illinois Licensed ACM inspector to satisfy State of Illinois requirements prior to demolition.	1 (includes 18 buildings plus walkways)	\$ _____
2. Abatement of special waste materials from buildings in Group 5 in preparation for demolition	Remove and dispose/recycle off-site :  ACM ROOFING, SIDING, FLOOR TILE and other ACM identified by the inspection in line item 1. Also include all PCB ballasts, fluorescent and mercury bulbs. Remove, Recycle and or dispose all misc. debris in and around buildings as needed in order to complete hazardous material disposal.	Footprint of 18 buildings total approx. 27,222 square feet PLUS 750 linear feet of transite covered walkways	\$ _____
	<b>GRAND TOTAL</b>		\$ _____

**Detailed breakdown of Item 2 above.**

GROUP 5		Building Footprint SQFT	Comments	TOTAL cost
5-1	Fulminate Service Magazine	183	-	
5-2	Fulminate Heater House	183	-	
5-3	Fulminate Dry House	304	-	
5-4	Fulminate Screen & Blend	1,831	Additional transite wall around perimeter	

5-5	Primer Loading	5,286	Interior transite ceiling	
5-6	Delay Loading	4,354	Interior transite ceiling	
5-7	Powerhouse	1,452	1.5 story height	
5-8	Change House	7,534	Partial floor tile	
5-10	Black Powder Dry House	304	-	
5-11	Black Powder Htr House	183	-	
5-12	Black Powder Service Mag	183	-	
5-13	Primer Dry House	808	-	
5-16	Jumble & Jolt Fuse Test	1,087	-	
5-20	Change House	1,560	-	
5-29 B	Clock house	200	-	
5-30	Vacuum Pump Houses (5 each)	32	-	
5-31	Booster Storage Magazine	582	-	
5-32	Unloading Ramp & Deck	0.00	Building 5-32 can be deleted, no special wastes have been identified there.	NOT IN CONTRACT
750 Lin. Ft.	Covered Walkways - While some are full 3-sided transite walkways, others are a single wall beneath the roof overhang at the perimeter of the building (such as Building 5-6), still others have transite roofs with metal panel side walls. All transite is to be removed and costs are to be included in either the walkway item or with the building adjacent to the walkway, but not both.	4,500	Typically ,2 walls and roof are transite	
All Structures	TOTAL FOOTPRINT SQUARE FOOTAGE	30,694		\$ _____