

PART I - SCHEDULE OF ITEMS updated 5/24/23

SECTION B - SERVICES AND PRICES

PINTLER DISTRICT RANGER STATION WATER DISTRIBUTION SYSTEM DESIGN

Beaverhead-Deerlodge National Forest

Pintler Ranger District

Granite County, Montana

B-1 (Updated) - SCHEDULE OF ITEMS

ITEM NO.	DESCRIPTION	PAY UNIT	QTY. TYPE	EST. QTY.	UNIT PRICE	TOTAL PRICE
1	Mobilization	Lump Sum	AQ	All	\$_____	\$_____
2	Construction Survey and Staking	Lump Sum	AQ	All	\$_____	\$_____
3	6-Inch Waterline, PVC	Foot	AQ	10	\$_____	\$_____
4	4-Inch Waterline, Polyethylene (Open-cut installation)	Foot	AQ	500	\$_____	\$_____
6	2-Inch Waterline, Polyethylene (Open-cut installation)	Foot	AQ	150	\$_____	\$_____
7	1-1/2-Inch Waterline, Polyethylene (Open-cut installation)	Foot	AQ	100	\$_____	\$_____
8	1-Inch Waterline, Polyethylene (Open-cut installation)	Foot	AQ	420	\$_____	\$_____
10	4-Inch Valve, Gate w/Box	Each	AQ	1	\$_____	\$_____
11	2-Inch Valve, Gate w/Box	Each	AQ	1	\$_____	\$_____
12	2-Inch Valve, Curb w/ Box	Each	AQ	1	\$_____	\$_____
13	1-1/2-Inch Valve, Curb w/ Box	Each	AQ	1	\$_____	\$_____
14	1-Inch Valve, Curb w/ Box	Each	AQ	2	\$_____	\$_____
15	6" Fire Hydrant w/ Auxiliary Gate Valve	Each	AQ	1	\$_____	\$_____
16	1-inch Frost-Free Hydrant w/ Backflow Preventer	Each	AQ	2	\$_____	\$_____
17	6" x 6" Tee	Each	AQ	1	\$_____	\$_____
18	6" x 4" Tee	Each	AQ	1	\$_____	\$_____
19	4" x 4" Tee	Each	AQ	1	\$_____	\$_____
20	4" x 2" Tee	Each	AQ	4	\$_____	\$_____
21	2" x 2" Tee	Each	AQ	1	\$_____	\$_____
22	1" x 1" Tee	Each	AQ	2	\$_____	\$_____

23	4" x 1-1/2" Reducer	Each	AQ	1	\$_____	\$_____
24	4" x 1" Reducer	Each	AQ	1	\$_____	\$_____
25	2" x 1" Reducer	Each	AQ	1	\$_____	\$_____
26	2" Blind Flange	Each	AQ	2	\$_____	\$_____
27	4" x 90° Bend	Each	AQ	1	\$_____	\$_____
28	4" x 11.25° Bend	Each	AQ	3	\$_____	\$_____
29	1" x 90° Bend	Each	AQ	3	\$_____	\$_____
30	6" Cap	Each	AQ	1	\$_____	\$_____
31	Remove Existing Meter Pits	Lump Sum	AQ	All	\$_____	\$_____
32	Water Meter and Pressure Reducing Valve Vault	Each	AQ	1	\$_____	\$_____
33	Install 2" Service into Garage/Shop w/ Demolition and Rehab	Lump Sum	AQ	All	\$_____	\$_____
34	Install 1-1/2" Service into District Office w/ Demolition and Rehab	Lump Sum	AQ	All	\$_____	\$_____
35	Install 1" Service into Warehouse/Garage w/ Demolition and Rehab	Lump Sum	AQ	All	\$_____	\$_____
36	Connect to Existing 2" Curb Stop at Bunkhouse	Lump Sum	AQ	All	\$_____	\$_____
37	Connect to Existing Horse Waterer	Lump Sum	AQ	All	\$_____	\$_____
38	Remove Existing Hydrants	Lump Sum	AQ	All	\$_____	\$_____
39	Type C Surface Restoration	LF	AQ	955	\$_____	\$_____
40	Asphalt Patching	LF	AQ	270	\$_____	\$_____

B-2 NOTES: Payment for bond premiums in accordance with Clause 52.232-5, Payments under Fixed-Price Construction Contracts, shall not be in addition to the contract price. Include bond payments under Pay Item #1 Mobilization.

One award will be made from this solicitation, contractors must submit pricing for all items.

Price quotation furnished by:

Vendor Name _____ Phone (____) _____

Contact Name & E-mail _____ UEI # _____